

Master Planned Communities, Land Planning, Site Planning & Design, Environmental Analysis & Landscape Architecture

Project Narrative The Villas at The Boulders

A Luxury Live/Work Community Request for Development Review

and Preliminary Plat Approval

(Boulders Commercial Parcels A & B)

Revised 2-12-2004

LOCATION AND CONTEXT

The Boulders Resort and Golf Community is one of Scottsdale's oldest and most respected master-planned mixed-use communities. The latest revision to the Development Master Plan was case 5-ZN-92, which set residential densities and provided for commercial areas along Scottsdale Road known as the "Boulders Commercial Parcels." These parcels are roughly 25% developed, with the unique El Pedregal retail/arts center, Desert Foothills Medical Center, and a real estate office. South of Westland Road on Scottsdale Road (in what is now the Winfield Community) the Westland Carefree Office Center has been approved and is currently nearing completion.

The Development Master Plan case 5-ZN-92 established two zoning categories for Boulders Commercial Parcels:

- PNC (Planned Neighborhood Center) on Parcel A, about 14 acres, allowing a variety of commercial uses and up to 4 dwelling units per gross acre, and
- C-2 (Central Business District, Parcel B), originally 22 acres and now including El Pedregal, the medical center and the real-estate office, allowing a variety of commercial uses and up to 49 dwelling units by stipulation in 5-ZN-92.

The Site Plan for Boulders Villas (Case 5-ZN-1992#3, December 2003), was supported by the Boulders HOA and was approved by the Planning Commission and City Council. That case contains stipulations that apply to this Development Review. This action was preceded by a full citizen involvement program and extensive contact with the Boulders Homeowners Association.

Note that a concurrent Preliminary Plat application is being submitted for the platrelated aspects of Boulders Villas.

Approval for the "live/work" Boulders Villas project recognized that this type of use better serves the Boulders setting, greatly reduces traffic volumes, lowers building heights from what is allowed for commercial structures, reduces adverse visual impacts, and provides a type of use that is uniquely suited to the seasonal or permanent resident who wishes to carry out business activity in a gated, integrated office/home environment.

REQUEST

The applicant is requesting design approval for 48 "live/work" units occupying all of the PNC zone and about 4 acres of the C-2 zone, and a clubhouse to be located in the PNC portion.

Note that the planned Nursery Yard lot has been transferred to Wyndham International/Boulders Joint Venture LLC and will be the subject of a subsequent Development Review application. It is no longer included in this Boulders Villas request.

The architecture developed by Douglas Fredrickson Architects is very sensitive to the Boulders Community context and presents a modified Southwest/Pueblo style with rounded stucco exterior walls, flat roofline, wood garage doors, ornamental shaded porticoes, internal courtyards, and a full integration of the business space with the living space. Please see floor plans, elevations and color samples provided.

The live/work unit is available in three styles with optional upgrades. About 300 s.f. of separate-entry office space is provided, with from 1300 to 2000 s.f. of living space and 300 to 400 s.f. of patio/courtyard space. Each unit has a double garage and parking for the office use.


In addition, the southern 40-unit complex provides a 2,300 s.f. clubhouse that offers a pool and large covered patio, as well as both recreational and business-support functions within the building. See the floor-plan and elevations provided.

The site plan, as approved by City Council, provides ample buffering from the residential portion of The Boulders (along Boulders Parkway), along Westland Road, and also provides a wide Scenic Corridor along Scottsdale Road. The approved site plan meets Boulders Development Plan N.A.O.S. requirements and the requirements of the PNC (Planned Neighborhood Center) and C-2 zoning, and also conforms to stipulations from the original 5-ZN-1992 Master Plan zoning case.

Lighting is low-level comprised exclusively of "Boulders" style full-cut-off bollard lighting; sconce lighting on buildings; and a lighted mailbox/address structure at each unit. Low-voltage landscape lighting is used at the project entries.

Landscape material consists of native species, in keeping with Boulders landscape character. No lawns or water features are proposed. Entry gates and walls use the same design found at the Boulders entries off Westland Road, and all signage will be consistent with signage currently in use at The Boulders.

In summary, this unique "live/work" community will be visually and texturally harmonious with existing Boulders commercial and residential development, and will be an attractive completion of these prominent commercially-zoned parcels.



Boulders Villas offers à unique, gaind office/residential setting for seasonal or year-doued business/residential use that combines a cesidential villa with a separate-entry office space. The Clubhouse offers in addition to recidential areamentes a meeting room and business support facilities.

Site Plan Obla: Zoning: C-2 PCD SSL, horth portion; PNC PCD ESI, south portion; Zoning Case: All adjacent property: 5-29-92 (Boulders Master Development Plan): Site Plan Approval for Villas 5-29-9293 (12-2003)

Approx. gross floor areas: Livelwork units: Stesidence: 1319 to 2037 s.f. Office: 241 to 325 s.f. Garage 531 to 582 s.f. Chibbouse: 2,361 s.f. Chibbouse: 2,361 s.f.

Parisel sizer: PNC (south unit) 14.1 acres per DMP, C-2 (north unit) 4 acres. Residential Unities: 48 (8 north, 41 south) Residential Unities: 27 DUIAC Parking required; 2 pler residential unit, 1 per office unit, Cabhouses 11 spaces. See Sketch submitted to show how ACA spaces are accommodated, Total 155 spaces Required. Building Height: 30' allowed per 5-ZN-1992 to natural grade, 224/- provided above FFE. All one story.

Open space required is exceeded by N.A.O.S. fequired (25% of site per OMP), 18.1 Ac. x 25 %= 4.52 Ac.

50% of open spoad fequired is provided in peripheral buffers and Scenic Comdor. Sites do not abut single family districts (separated by roadway from residential or adjacent to C-2 zoned land)

PNG properly size was created in 5-ZN-92, and is segmented into 2 sub-parcels approximately 5 fi acres and 8.5 acres.

Roadway widths: 2.7 pavement with 16° foll-curb adjacent to parking, 20' pavement with 16" roll-curb if parking not adjacent. Parking stalls 10" x 16' typicat

See architectural plans and elevations.

The commercial parcels are not subject to Boulders design guidelines and are governed by separate CDARs. but walls, also features and paving will conform to the "Boulders Character" by using organic shapes, muted earth-tone colors, and kw-key signage. "Boulders" bottland lights and lighted malbouxideliness structures at each unit are used, with 12V landscape lighting at entries and remote signs. See separate lighting exhibit and photometrics.

February 12, 2004

Owner Boulders Joint Venture LLC/ Wyndham International Developer: Watt/Solus LLC Land Planner/Landscape Architect: LVA Urban Design Studio LLC Architect: Douglas Fredrickson Architects. Civil Engineer: SKG Enterprises

Boulders Villas

Luxury Live/Work Office/Residential Units GENERAL Site Plan



